



Acoustical Testing Laboratory



Accredited by the National Voluntary
Laboratory Accreditation Program
for the specific scope of accreditation
under Lab Code 200291

TEST REPORT

for

Protecto Wrap Company
2255 South Delaware Street
Denver, CO 80223
Marc Lester / 303 777-3001

Impact Sound Transmission Test
ASTM E 492 - 90 / ASTM E 989 - 89
On

**8" Concrete Slab and Suspended Gypsum Board Ceiling Overlaid with;
Hardwood Flooring over WhisperMat HW Membrane Underlayment**

Page 1 of 4

Report Number: NGC 7003031

Assignment Number: G-183

Specimen Receipt Date: NA

Test Date: 06/24/2003

Report Date: 07/10/2003

Submitted by:

Craig G. Cooper
Craig G. Cooper
Test Engineer

Reviewed by:

Robert J. Menchetti
Robert J. Menchetti
Director

The results reported above apply to specific samples submitted for measurement.


No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's accreditation or any of its test reports in no way constitutes or implies product certification, approval, or endorsement by NVLAP or any agency of the U.S. Government.



Acoustical Testing Laboratory



Accredited by the National Voluntary
Laboratory Accreditation Program
for the specific scope of accreditation
under Lab Code 200291

Page 2 of 4

Report Number: NGC 7003031

Test Method: This test method is in accordance with American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine - Designation: E 492 - 90.

Specimen Description: 8" Concrete Slab and Suspended Gypsum Board Ceiling Overlaid with; Hard Flooring over, according to client, WhisperMat HW Membrane Underlayment.

The test specimen was a floor-ceiling assembly consisting of the following:

- 1 layer of 7/16" thick T&G hardwood flooring, 2-3/8" wide planks (1.47 PSF), from BERTL Description; Rovere N. Flooring attached to membrane using Franklin Adhesive 211 wood flooring adhesive with 1/4" x 1/4" V notched trowel.
- 1 layer of 0.20" thick WhisperMat HW asphalt membrane floor underlayment with foam side up. (0.26 PSF) Membrane was self-adhered to kraft paper that is adhered to the concrete at the perimeter and tapping machine areas with double-sided tape.
- 8" thick reinforced concrete slab (85.6 PSF).
- Suspended ceiling system consisting of nominal 5/8" type X gypsum board (2.3 PSF) attached with 1-1/8" screws, 12" o.c. to suspended Rigid X ceiling grid system. 10" plenum with 6" of lay-in fiberglass insulation (0.23 PSF).

The overall weight of the test assembly is 89.86 PSF.

The perimeter of the concrete slab was sealed with fiber gasketing and a sand filled trough. The test assembly is structurally isolated from the receiving room. The ceiling joints were taped.

Specimen size: 12 ft x 16 ft.

Conditioning: Adhesive cured for a minimum of 1 hour. Concrete slab cured for a minimum of 28 days.

Test samples were submitted by client and tested as received.

Test Results: The results of the tests are given on pages 3 and 4.

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's accreditation or any of its test reports in no way constitutes or implies product certification, approval, or endorsement by NVLAP or any agency of the U.S. Government.

Normalized impact sound pressure level

Test: ASTM E 492 - 90 / ASTM E 989 - 89

Page 3 of 4

Test Number: NGC7003031

Date: 06/24/2003

Size: 17.84 m²

Source room

Receiving room

Volume V = 45.71 m³

Temperature [°C]: 23.4

Temperature [°C]: 21.9

Humidity [%]: 80

Humidity [%]: 55

Impact Insulation Class IIC = 72 dB

Sum of unfavourable deviations: 14.0 dB

Max. unfavourable deviation: 8.0 dB at 125 Hz

Frequency	L _n	L ₂	T	Corr.	u.Dev.	ΔL _n
[Hz]	[dB]	[dB]	[s]	[dB]	[dB]	
100	40.0	45.3	2.45	-5.3	-	0.260
125	48.0	53.5	2.66	-5.5	8.0	0.290
160	41.0	48.0	3.76	-7.0	1.0	0.266
200	45.0	51.0	3.10	-6.0	5.0	0.116
250	38.0	44.3	3.08	-6.3	-	0.122
315	33.0	39.8	3.13	-6.8	-	0.091
400	29.0	35.2	2.96	-6.2	-	0.110
500	31.0	36.3	2.75	-5.3	-	0.069
630	33.0	38.5	2.70	-5.5	-	0.064
800	28.0	34.0	2.72	-6.0	-	0.053
1000	24.0	29.9	2.65	-5.9	-	0.042
1250	26.0	31.0	2.39	-5.0	-	0.045
1600	23.0	28.0	2.17	-5.0	-	0.039
2000	19.0	22.9	1.87	-3.9	-	0.041
2500	16.0	19.3	1.66	-3.3	-	0.039
3150	14.0	17.2	1.58	-3.2	-	0.044
4000	12.0	14.5	1.43	-2.5	-	0.036
5000	11.0	13.5	1.29	-2.5	-	0.030

L_n = Normalized Sound Pressure Level, dB

L₂ = Receiving Room Level, dB

T = Reverberation Time, seconds

ΔL_n = Uncertainty for 95% Confidence Level

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's accreditation or any of its test reports in no way constitutes or implies product certification, approval, or endorsement by NVLAP or any agency of the U.S. Government.

Normalized impact sound pressure level

Test: ASTM E 482 - 90 / ASTM E 989 - 89


Page 4 of 4

Test Number: NGC7003031

Date: 06/24/2003

Impact Insulation Class IIC = 72 dB

Frequency	L_n
[Hz]	[dB]
100	40
125	48
160	41
200	45
250	38
315	33
400	29
500	31
630	33
800	28
1000	24
1250	26
1600	23
2000	19
2500	16
3150	14
4000	12
5000	11



- Due to high insulating value of specimen, background levels limit results at these frequencies.

L_n = Normalized Sound Pressure Level, dB

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's accreditation or any of its test reports in no way constitutes or implies product certification, approval, or endorsement by NVLAP or any agency of the U.S. Government.



Acoustical Testing Laboratory

TEST REPORT

for

Protecto Wrap Company
2255 South Delaware Street
Denver, CO 80223
Marc Lester / 303 777-3001

Sound Transmission Loss Test
ASTM E 90 - 02
On

**8" Concrete Slab and Suspended Gypsum Board Ceiling Overlaid with;
Hardwood Flooring over WhisperMat HW Membrane Underlayment**

Page 1 of 4

Report Number: NGC 5003012

Assignment Number: G-183

Specimen Receipt Date: NA

Test Date: 06/24/2003

Report Date: 07/10/2003

Submitted by:

Craig G. Cooper
Craig G. Cooper
Test Engineer

Reviewed by:

Robert J. Menchetti
Robert J. Menchetti
Director

The results reported above apply to specific samples submitted for measurement.
No responsibility is assumed for performance of any other specimen.
This report may not be reproduced except in full, without the written approval of the laboratory.
The laboratory's test reports in no way constitutes or implies product certification, approval,
or endorsement by this laboratory.



Acoustical Testing Laboratory

Page 2 of 4

Report Number: NGC 5003012

Test Method: This test method generally follows * the American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements - Designation: E 90 - 02.

Specimen Description: 8" Concrete Slab and Suspended Gypsum Board Ceiling Overlaid with; Hard Flooring over, according to client, WhisperMat HW Membrane Underlayment.

The test specimen was a floor-ceiling assembly consisting of the following:

- 1 layer of 7/16" thick T&G hardwood flooring, 2-3/8" wide planks (1.47 PSF), from BERTL Description; Rovere N. Flooring attached to membrane using Franklin Adhesive 211 wood flooring adhesive with 1/4" x 1/4" V notched trowel.
- 1 layer of 0.20" thick WhisperMat HW asphalt membrane floor underlayment with foam side up. (0.26 PSF) Membrane was self-adhered to kraft paper that is adhered to the concrete at the perimeter and tapping machine areas with double-sided tape.
- 8" thick reinforced concrete slab (85.6 PSF).
- Suspended ceiling system consisting of nominal 5/8" type X gypsum board (2.3 PSF) attached with 1-1/8" screws, 12" o.c. to suspended Rigid X ceiling grid system. 10" plenum with 6" of lay-in fiberglass insulation (0.23 PSF).

The overall weight of the test assembly is 89.86 PSF.

The perimeter of the concrete slab was sealed with fiber gasketing and a sand filled trough. The test assembly is structurally isolated from the receiving room. The ceiling joints were taped.

Specimen size: 12 ft x 16 ft.

Conditioning: Adhesive cured for a minimum of 1 hour. Concrete slab cured for a minimum of 28 days.

Test samples were submitted by client and tested as received.

Test Results: The results of the tests are given on pages 3 and 4.

* Tests conducted in Floor-Ceiling chambers do not meet all requirements of the most recent ASTM E 90 Standard.

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's test reports in no way constitutes or implies product certification, approval, or endorsement by this laboratory.

Acoustical Testing Laboratory

Sound Transmission Loss Test Data

Page 3 of 4

Per: ASTM E 90 - 02 / ASTM E 413 - 87

No. of test report: NGC5003012

Test Date: 06/24/2003

Size: 17.8 m²

Temperature [°C]: 21.9

Sound Transmission Class STC = 71 dB

Sum of unfavourable deviations: 29.0 dB

Max. unfavourable deviation: 8.0 dB at 200 Hz

Frequency	STL	L1	L2	T	Corr.	u.Dev.	ΔSTL
[Hz]	[dB]	[dB]	[dB]	[s]	[dB]	[dB]	
100	50	104.8	62.2	2.45	7.7	-	1.100
125	48	99.9	59.9	2.66	8.1	7.0	1.459
160	53	101.5	58.4	3.76	9.6	5.0	0.742
200	53	99.1	54.8	3.10	8.8	8.0	0.548
250	58	99.5	49.8	3.08	8.7	6.0	0.346
315	69	100.2	40.5	3.13	8.8	-	0.566
400	73	102.9	38.7	2.96	8.6	-	0.346
500	73	101.5	36.7	2.75	8.3	-	0.877
630	69	99.0	37.7	2.70	8.2	3.0	0.300
800	77	98.9	29.7	2.72	8.2	-	0.141
1000	82	97.9	24.4	2.65	8.1	-	0.663
1250	84	99.0	22.9	2.39	7.6	-	0.200
1600	84	99.7	23.2	2.17	7.2	-	0.469
2000	87	101.1	20.2	1.87	6.6	-	0.173
2500	92	102.9	17.3	1.66	6.1	-	0.361
3150	94	103.4	15.4	1.58	5.8	-	0.374
4000	94	102.0	13.7	1.43	5.4	-	0.400
5000	90	96.5	11.6	1.29	5.0	-	0.557

STL = Sound Transmission Loss, dB

L1 = Source Room Level, dB

L2 = Receiving Room Level, dB

T = Reverberation Time, seconds

Δ STL = Uncertainty for 95% Confidence Level

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's test reports in no way constitutes or implies product certification, approval, or endorsement by this laboratory.

Acoustical Testing Laboratory

Sound Transmission Loss Test Data

Page 4 of 4

Per: ASTM E 90 - 02 / ASTM E 413 - 87

No. of test report: NGC5003015


Test Date: 06/27/2003

Size: 17.8 m²

Temperature [°C]: 22.8

Sound Transmission Class STC = 72 dB

Frequency [Hz]	STL [dB]	ΔSTL
100	51	1.225
125	48	1.237
160	53	0.877
200	54	0.714
250	60	0.387
315	68	0.632
400	74	0.200
500	76	0.756
630	72	0.489
800	79	0.316
1000	83	0.332
1250	85	0.265
1600	85	0.316
2000	89	0.173
2500	92	0.173
3150	95	0.346
4000	94	0.361
5000	88	0.374



* Due to high insulating value of specimen, background levels limit results at these frequencies.

STL = Sound Transmission Loss, dB
 Δ STL = Uncertainty for 95% Confidence Level

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's test reports in no way constitutes or implies product certification, approval, or endorsement by this laboratory.