



G0665.12-113-11-R1 ACOUSTICAL PERFORMANCE TEST REPORT ASTM E 90, ASTM E 492, ASTM E 2179

Rendered to

PROTECTO WRAP COMPANY

Series/Model: Protecto Wrap Whispermat LVT

Specimen Type: Concrete Slab - 152 mm

Overall Size: 3023 mm by 3632 mm

STC 51 IIC 57 ΔIIC 27

Test Specimen Identification:

Floor Topping: 4 mm Luxury Vinyl Plank

Floor Underlayment: 1.8 mm Protecto Wrap Whispermat LVT

Floor Slab: 152 mm Concrete Slab

Reference should be made to Intertek-ATI Report G0665.12-113-11 for complete test specimen description. This page alone is not a complete report.





G0665.12-113-11-R1 Page 1 of 4

Acoustical Performance Test Report

PROTECTO WRAP COMPANY 1955 South Cherokee Street Denver, Colorado 80223

Report G0665.12-113-11
Test Date 07/11/16
Report Date 05/10/18
Revision Date 05/23/18

Project Scope

This report is a reissue of the original Report No. G0665.04-113-11 and is rendered to Protecto Wrap Company through written authorization. A summary of the results is listed in the Test Results section, and the complete test data is included as attachments to this report. The original client provided the test specimen.

Test Methods

The acoustical tests were conducted in accordance with the following standards. The equipment listed in the attachments meets the requirements of the following standards.

ASTM E 90-09, Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions

ASTM E 413-10, Classification for Rating Sound Insulation

ASTM E 492-09(2016)e1, Standard Test Method for Laboratory Measurement of Impact Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine

ASTM E 2179-03(2016), Standard Test Method for Laboratory Measurement of the Effectiveness of Floor Coverings in Reducing Impact Sound Transmission Through Concrete Floors

ASTM E 989-06 (2012), Classification for Determination of Impact Insulation Class (IIC)

ASTM E 2235-04 (2012) Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods

Test Procedure

All testing was conducted in the VT test chambers at Intertek-ATI located in York, Pennsylvania. The microphones were calibrated before conducting the tests.

The airborne transmission loss test was conducted in accordance with the ASTM E 90 test method using the single direction method. Two background noise sound pressure level and five sound absorption measurements were conducted at each of five microphone positions. Four sound pressure level measurements were made simultaneously in both rooms, at each of five microphone positions.





Test Procedure (Continued)

The impact sound transmission test was conducted in accordance with the ASTM E 492 test method. Two background noise sound pressure level, two sound pressure level measurements with the tapping machine operating at each position specified by ASTM E 492, and five sound absorption measurements were conducted at each of five microphone positions.

The air temperature and relative humidity conditions were monitored and recorded during all measurements.

Test Conditions

Source Room		Receive Room		
Average Temperature 22.1°C		Average Temperature	22.4°C	
Average Relative Humidity	58%	Average Relative Humidity	61%	

Test Calculations

The STC (Sound Transmission Class), IIC (Impact Insulation Class), and Δ IIC (Delta Impact Insulation Class) ratings were calculated in accordance with ASTM E 413, ASTM E 989, and ASTM E 2179, respectively.

Test Specimen Materials and Installation Details

Material	Dimensions (mm)	Thickness (mm)	Manufacturer and Series Quantity		Average Weight			
I amount Wined Blank	914.4 by 152.4	4.0	N/A	10.98 m²	7.52 kg/m²			
Luxury Vinyl Plank	Note: Installed with releasable self-adhesive							
Whispermat LVT	914 by 3048	1.8	Protecto Wrap	10.98 m²	0.76 kg/m²			
	Note: Loose laid							
Concrete Slab	3023 by 3632	152.0	N/A	10.98 m²	366.18 kg/m ²			
	Note: The concrete slab was installed in a test frame flush to the source room.							

Comments

The total weight of the floor/ceiling assembly was 4111.6 kg. Intertek-ATI will store samples of the test specimen for four years. Photographs of the test specimen are included in the attachments. A drawing of the test specimen is included in the attachments.





G0665.12-113-11-R1 Page 3 of 4

This report is reissued in the name of Protecto Wrap Company through written authorization from the original report holder. The original Report No. is G0665.04-113-11.

Intertek-ATI will service this report for the entire test record retention period. Test records, such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained by Intertek-ATI for the entire test record retention period. The test record retention period ends four years after the test date.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen tested. This report is intended to help in the client's quality assurance program, but it does not represent a continuous or exhaustive evaluation of the specimen tested or of other products or materials that were not evaluated. The statements and data provided herein do not constitute approval, disapproval, certification, or acceptance of performance or materials.

This report may not be reproduced, except in full, without the written approval of Intertek-ATI.

FOR INTERTEK-ATI:

Cody R. Snyder

Cody R. Snyder

Jordan Strybos

Cody R. Snyder Technician I - Acoustical Testing

Project Manager - Acoustical Testing

Attachments (9 Pages): This report is complete only when all attachments are included.

* Stated by Client/Manufacturer N/A - Non Applicable



G0665.12-113-11-R1

Page 4 of 4

Revision Log

Revision	Date	Page(s)	Description
R0	05/10/18	N/A	Original Report Issue - Reissue of Report No. G0665.04-113-11 in the name of Protecto Wrap Company.
R1	05/23/18	All pages	ASTM E2179 data added





Attachments

Instrumentation

Manufacturer	Model	ATI Number	Date of Calibration
National Instruments	PXI-1033	65124	06/16 *
Norsonie	1251	INT00127	01/16
PCB Piezontronics	378B20	63748	06/16
PCB Piezotronics	378B20	63744	06/16
PCB Piezotronics	378B20	63745	06/16
PCB Piezotronics	378C20	65617	06/16
PCB Piezotronics	378B20	63747	06/16
Comet	T7510	63810 63811	10/15 10/15
PCB Piezotronics	378B20	63738	05/16
PCB Piezotronics	378B20	63739	05/16
PCB Piezotronics	378B20	63740	05/16
PCB Piezotronics	378B20	63742	05/16
Scantek	378B20	63741	05/16
Comet	T7510	63812	11/15
Look Line s.r.l.	EM50 (TM50)	65351	02/16
	National Instruments Norsonic PCB Piezontronics PCB Piezotronics PCB Piezotronics PCB Piezotronics PCB Piezotronics PCB Piezotronics Comet PCB Piezotronics PCB Piezotronics PCB Piezotronics Scantek Comet	National Instruments PXI-1033 Norsonic 1251 PCB Piezontronics 378B20 PCB Piezotronics 378B20 Scantek 378B20 Comet T7510	National Instruments PXI-1033 65124 Norsonic 1251 INT00127 PCB Piezontronics 378B20 63748 PCB Piezotronics 378B20 63744 PCB Piezotronics 378B20 63745 PCB Piezotronics 378C20 65617 PCB Piezotronics 378B20 63747 Comet T7510 63810 PCB Piezotronics 378B20 63738 PCB Piezotronics 378B20 63740 PCB Piezotronics 378B20 63742 Scantek 378B20 63741 Comet T7510 63812

^{*} The calibration frequency for this equipment is every two years per the manufacturer's recommendation.

Test Chambers

VT Receive Room Volume	158.86 m³
VT Source Room Volume	190 m³









Page 2 of 9

AIRBORNE SOUND TRANSMISSION LOSS ASTM E 90

Test Date 07/11/16

Data File No. G0665.04

Client Protecto Wrap Company

Description 4 mm Luxury Vinyl Plank, 1.8 mm Protecto Wrap Whispermat LVT, 152 mm Concrete Slab

Specimen Area 10.98 m²

Technician Cody R. Snyder

Freq	Background	Absorption	Source	Receive	Specimen	95%	Number
	SPL		SPL	SPL	TL	Confidence	of
(Hz)	(dB)	(m^2)	(dB)	(dB)	(dB)	Limit	Deficiencies
80	38.9	14.8	109	67	42	3.70	-
100	35.5	12.4	107	67	40	1.60	-
125	37.1	9.4	106	70	38	1.10	0
160	26.9	8.5	107	72	37	1.90	1
200	24.6	11.1	104	72	33	2.20	8
250	24.2	10.9	104	64	40	1.00	4
315	23.9	9.7	105	62	44	0.60	3
400	19.1	8.0	104	61	44	0.20	6
500	22.8	7.5	104	57	49	0.40	2
630	18.6	7.2	104	53	53	0.40	0
800	17.7	7.0	105	49	59	0.40	0
1000	15.3	6.9	104	44	63	0.40	0
1250	9.4	7.0	104	42	66	0.20	0
1600	6.1	7.0	104	40	67	0.20	0
2000	4.2	7.7	104	38	68	0.30	0
2500	4.1	8.7	102	36	68	0.30	0
3150	4.0	9.6	103	34	70	0.40	0
4000	4.6	11.0	104	33	72	0.50	0
5000	5.2	12.9	104	32	72	0.50	-
6300	5.8	16.7	97	27	69	0.70	-
8000	6.2	22.0	97	20	75	0.80	-
10000	6.4	26.7	92	11	79	0.70	-

STC Rating 51 (Sound Transmission Class)
Deficiencies 24 (Sum of Deficiencies)

Notes: 1) Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.

2) Specimen TL levels listed in red indicate the lower limit of the transmission loss.

3) Specimen TL levels listed in green indicate that there has been a filler wall correction applied

ATI 00614 Revised 02/09/15








AIRBORNE SOUND TRANSMISSION LOSS ASTM E 90

Test Date	07/11/16
Data File No.	G0665.04
Client	Protecto Wrap Company
Description	4 mm Luxury Vinyl Plank, 1.8 mm Protecto Wrap Whispermat LVT, 152 mm Concrete Slab
Specimen Area	10.98 m ²
Technician	Cody R. Snyder











IMPACT SOUND TRANSMISSION

ASTM E 492

Test Date	07/11/16
Data File No.	G0665.04
Client	Protecto Wrap Company
Description	4 mm Luxury Vinyl Plank, 1.8 mm Protecto Wrap Whispermat LVT, 152 mm Concrete Slab
Specimen Area	10.98 m^2
Technician	Cody R. Snyder

Freq	Background SPL	Absorption	Normalized Impact	I	Number
			SPL	Confidence	of
(Hz)	(dB)	(m ²)	(dB)	Limit	Deficiencies
80	37.6	15.9	53	2.8	-
100	32.8	12.6	54	3.1	0
125	38.1	9.6	54	1.8	0
160	25.8	8.9	56	1.2	1
200	21.6	10.9	63	2.5	8
250	22.0	10.3	60	0.8	5
315	21.5	9.2	56	1.2	1
400	17.1	7.9	52	0.4	0
500	22.4	7.4	46	0.9	0
630	19.2	7.3	42	0.5	0
800	18.7	7.0	40	0.9	0
1000	15.3	6.9	36	1.2	0
1250	9.7	7.0	29	0.6	0
1600	6.9	7.1	25	0.5	0
2000	5.7	7.7	19	0.6	0
2500	5.1	8.7	14	1.0	0
3150	4.7	9.6	7	0.6	0
4000	5.4	11.0	5	0.5	-
5000	5.9	12.9	5	0.5	-
6300	6.6	16.5	6	0.6	-
8000	7.0	22.1	8	0.7	-
10000	7.1	26.6	9	0.8	-

IIC Rating 57 (Impact Insulation Class)
Deficiencies 15 (Sum of Deficiencies)

Note: Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.

ATI 00615 Revised 02/09/15 Page 4 of 9








IMPACT SOUND TRANSMISSION

ASTM E 492

Test Date	07/11/16
Data File No.	G0665.04
Client	Protecto Wrap Company
Description	4 mm Luxury Vinyl Plank, 1.8 mm Protecto Wrap Whispermat LVT, 152 mm Concrete Slab
Specimen Area	10.98 m ²
Technician	Cody R. Snyder











DELTA IMPACT INSULATION

ASTM E 2179

Test Date	07/11/16
Data File No.	G0665.04
Client	Foam Solutions Inc
Description	4 mm Luxury Vinyl Plank, 1.8 mm Protecto Wrap Whispermat LVT, 152 mm Concrete Slab
Specimen Area	10.98 m^2
Technician	Cody R. Snyder

Form	Bkgrd	Absorption	Normalized	95%	Normalized	95%	Resulting	No. of
Freq	SPL	(Square	Impact SPL	Conf	Impact SPL	Conf	Array	Defici-
(Hz)	(dB)	Meters)	BARE (dB)	Limit	SPEC (dB)	Limit	$L_{ref,c}$	encies
100	32.8	12.6	56.8	0.7	53.6	1.0	64	7
125	38.1	9.6	57.7	1.3	53.5	0.3	63	6
160	25.8	8.9	62.2	1.7	56.5	1.9	62	5
200	21.6	10.9	70.3	1.3	63.5	2.0	62	5
250	22.0	10.3	68.0	2.3	59.7	2.2	61	4
315	21.5	9.2	68.1	2.7	55.6	1.9	57	0
400	17.1	7.9	69.1	1.3	52.2	0.8	53	0
500	22.4	7.4	67.6	1.5	45.6	1.6	49	0
630	19.2	7.3	69.7	1.8	42.3	2.2	44	0
800	18.7	7.0	71.4	2.0	40.3	0.8	40	0
1000	15.3	6.9	71.5	2.6	35.8	0.3	36	0
1250	9.7	7.0	71.9	3.2	29.3	0.8	29	0
1600	6.9	7.1	72.6	3.3	24.9	1.0	24	0
2000	5.7	7.7	73.3	3.3	19.1	0.6	18	0
2500	5.1	8.7	73.0	3.0	13.7	1.0	13	0
3150	4.7	9.6	72.5	2.3	7.3	0.3	7	0

AIIC Rating 27 (Delta Impact Insulation Class)

Deficiencies 27 (Sum of Deficiencies)

Note: Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.

ATI 00756 Revised 02/09/15 Page 6 of 9








DELTA IMPACT INSULATION

ASTM E 2179

Test Date	07/11/16
Data File No.	G0665.04
Client	Foam Solutions Inc
Description	4 mm Luxury Vinyl Plank, 1.8 mm Protecto Wrap Whispermat LVT, 152 mm Concrete Slab
Specimen Area	10.98 m ²
Technician	Cody R. Snyder








Photographs



Source Room View of Test Specimen Installation



Receive Room View of Test Specimen Installation







Drawing



- 1-Floor Topping
- 2-Underlayment
- 3-Concrete Slab